

SRI GURU GOBIND SINGH COLLEGE OF COMMERCE  
PITAM PURA, (UNIVERSITY OF DELHI) DELHI-110034

Notice Inviting Quotation

Sealed Item rate quotations are invited from manufacturers of Power Control, Panels and LT Switch boards for following works. Quotation shall be quoted on letter head of Venders. Quotation shall be submitted in Principal Office, Sri Guru Gobind Singh College of Commerce in sealed cover, with profile & experience of such works on placed in separate cover by 22/10/2018 by 11 AM which shall be opened on same day at 11.30 AM.

1. Supply, Installation, Testing & Commissioning of Auto Transfer Switch (ATS), Panel size 2100 × 1025 × 1000 mm.
2. Supply, Providing & commissioning of 1000 Amp Aluminum bus bar trunking from New transformer to existing LT Panel.
3. Supply of 800 Amp Automatic Transfer Switch (ATS) with controller and MCCB 630 Amp 4P.

Details of Items and Terms & Conditions can be download from college website.

## Quotation

Name of Work: Supply, Installation, Testing & Commissioning of Auto Transfer Switch (ATS) Panel size 2100 × 1025 × 1000 mm

Item	Qty
1. Fabrication of Electrical Panel size of 2100 × 1025 × 1000 mm, 16 gauge MS sheet with, 800A Aluminum Busbar, Powder Coating and inter connection of Incoming and Outgoing in Existing Cubical Panel including Cartage, Loading and Unloading Complete.	1 No.
2. Fixing of 800 A 4P ATS and 630 A 4P MCCB with Inter connection in New ATS Panel as per site requirement.	1 No.

Note: GST extra as applicable

### Terms & Conditions:

1. Work is to be completed within 7 days of issue of work order.
2. ATS switches & MCCB shall be provided by college free of cost.
3. Installation shall be guaranteed for one year from the date of Commissioning against any defects.
4. 10% Security deposit shall be deducted which shall be released after defect liability period of one year.
5. 2% TDS for I.Tax shall be deducted from the bill of contractor as per Govt. rules.
6. Shut down if required shall be given as per feasibility with prior notice.
7. Panel shall be factory made with proper powder coating.

## Quotation

Name of Work: --Supply of 800A Automatic Transfer Switch and 630A 4P MCCB

Item	Qty
Supply of SOCOMEC ATYS 4X 800A W BRIDGING BARS (SOC95234080SL) including 6 no. Face Indication Lamp	1 Set
ATS CONTROLLER ATYS C20 for RTSE products	1 No.
L&T make 630A 4P MCCB of D Sine	1 No.

Note: GST extra as applicable

### Terms & Conditions:

1. Work is to be completed with 7 days of issue of work order.
2. Equipment shall be guaranteed for one year for date of commissioning against any defects.

## Quotation

Name of Work: --Supply , Installation, Testing & Commissioning of 1000A Aluminum Busbar Trunking from new Transformer to Existing LT Panel.

Items	Qty.
Supply, Installation, including suspension, testing and commissioning of following capacity Bus Trunking with Aluminum Busbar in 1.6 mm thick sheet enclosure in convenient sections for use on 3 phase, 4 wire, 415 volts, 50 Hz, A.C. supply including jointing of sections, flexible joints, expansion joints, bends and earthing with 2 runs of aluminum strips, suspenders, angle iron bracket, steel fasteners, connecting to earthing system etc. as required.	15 meter

Note: GST extra as applicable.

### Terms & Conditions:

1. Work is to be completed within 7 days of issue of work order.
2. Electrical Supply for Installation shall be provided by the college free of cost.
3. Installation shall be guaranteed for one year for date of commissioning against any defects.
4. 2% TDS for I.Tax shall be deducted from bill of contractor as per Govt. rules.
5. Shut down if required shall be given as per flexibility with prior notice.
6. Bus trunking shall be factory made with proper powder coating.